

April 17, 2020

**RFI  
FOR  
AIRFIELD MAINTENANCE COLD STORAGE BUILDING IFB 2020-05**

**AT  
SYRACUSE HANCOCK INTERNATIONAL AIRPORT  
SYRACUSE, NEW YORK**

RFI #:

1. Is the Project Prevailing Wage
  - a. Yes, this project is a prevailing wage project. The wage rates are located in the construction documents to indicate this.
2. Site Construction Fence
  - a. The Site construction fence must be NYS/OSHA approved fence to prevent access to the construction site.
3. Will Site Visits be allowed
  - a. An email will be distributed to all parties indicating the availability of the SRAA maintenance Supervisor to allow contractors access to the proposed construction site.
4. Detail D on drawing E-301 shows a new 100A three pole breaker to be installed to feed new panel PP-1 which shows on the panel schedule on drawing E-201 as having a 120A main circuit breaker. 120A is not a common size breaker. Should the feed breaker and PP-1 main breaker both be rated for 125A?
  - a. 125A breakers at each the feed breaker and main breaker are acceptable.
5. Panel Schedule on drawing E-201 details the panel as being a 3 wire, 1 phase configuration. The load calculations on the panel schedule reflect a 4 wire, 3 phase system. Detail D on drawing E-301 also shows conflicting information as to what is specifically needed. Please verify the new service is a 208/120V, 3 Phase, 4 wire (plus ground) design.
  - a. The panel schedule should read 3 phase 4 wire at the top.

port Authority

315.454.3263  
315.454.8757  
info@syraairport.org

1000 Col. Eileen Collins Blvd.  
Syracuse, NY 13212

- 6. Will it be allowed for spoils to remain on site?
  - a. Spoils may remain on site. They shall not be stock piled and must be used to grade the area around the new building. All building material debris, large rocks and or roots must be removed from the site. Only soil may remain on site to be tracked and graded.
  
- 7. Will Union Corrugating or Fabral PBR panels be allowed in lieu of Varco Pruden roof and wall panels?
  - a. Bid the project as shown – equal products are allowed

End:



