



1000 Col. Eileen Collins Blvd.
Syracuse, NY 13212

p – 315.454.3263
f – 315.454.8757
bids@syrairport.org

RFP #2024-07
ADDENDUM #04
Issued May 01, 2024

RFI #1

1.) The most recent issued addendum 3 – **RFI #6 - Addendum #02 RFI #2** “Please provide a laminate spec for P-LAM.”

Response to RFI #2 “See attached Exhibit.” P-LAM not found in attached Exhibit, please provide.”
Response to RFI #6 - There will be no P-LAM, only LVT and Carpet finishes.”

The question was directed towards material specification for casework and countertops as seen on DWG A201. Please confirm contractor is responsible to provide and install casework and countertops. If so, Please provide casework and countertop material specifications. For example, P-LAM (Plastic Laminate) , Solid Surface, Pre-Engineered wood, etc...

Response to RFI #1

There is no spec for a specific P-LAM in terms of casework and countertops. A grey laminate finish for any casework is sufficient and a darker grey laminate finish for countertops is acceptable.

RFI #2

Addendum 3 – **RFI 1 Response**- Please see image below for LVT Floor Finish.”

The image provided lacks information. After some research we were unable to identify the product based off the image provided. Please provide manufacturer and model # for LVT flooring

Response to RFI #2

Cobalt Surfaces, Kantanga LVT – Armor <https://cobaltsurfaces.com/katanga-loose-lay-and-glue-down-lvt/#>

NOTE: Clarification for addendum #1, RFI #3: There will be floor boxes located in the conference room area. Selected Contractor will be responsible for drilling and piping with the understanding they are responsible for making sure there is no obstructions within and below the slab when drilling. There must be power, data and tv hardware such as an HDMI connection to the TV location.

